BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/04/2014-15 Dated: 31-10-2014

APPROVED TENDER SCHEDULE –'B'

Item No: 54

Name of Work:-Improvements of drains in Santhosh Nagara 1st and 2nd cross roads in Attur ward no:03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri JAYANTH T GOWDA	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(Item no19.1,Page no138.PWD SR 2014-15)	Cum	116.40	70.00	Rupees seventy only
2	Removing B.S slab of drain and stacking	Sqm	597.80	55.00	Rupees fifty five only
3	Refixing stone slabs of drains and pointing in CM(1:3)	Sqm	597.80	70.00	Rupees seventy five only
4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete do 7.5 cms thick	Sqm	250.20	610.00	Rupees six hundred ten only
5	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/kanker/Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130.PWD SR 2014-15)	Cum	118.40	62.00	Rupees sixty two only
6	KSRB 5-14: Providing and constructing precast concrete solid blocks with compressive strength not less than 35Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (P25/5.27)	Sqm	88.00	980.00	Rupees nine hundred eighty only
7	KSRB 5-15: Providing and constructing Non load bearing wall with cement concrete solid blocks with compressive strength not less than 35Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x10x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (P25/5.28)	Sqm	88.00	700.00	Rupees seven hundred only

Bangalore Mahanagara Palike Print Count : 2

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri JAYANTH T GOWDA	
				Rate	Rate in Words
8	KSRRB 4.1:6Providing and laying in position plain cement concrete mix 1:2:4 with cement @240kgs,with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15cms thick well compacted,in foundation,plinth and cills,including cost of all materials, labour, HOM of machineries, curing complete as per specifications.Specification no4.1,4.2 (Page.12 & Item No. 4.6)	Cum	17.60	5175.00	Rupees five thousand one hundred seventy five only
9	Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate).	Sqm	396.00	1220.50	Rupees one thousand two hundred twenty and paise fifty only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.